

Key No. 25183 - I-15 RIVERTON ROAD BRIDGE
Bingham County

Item No	Description	QTY	Unit
104-005A	PARTNERING	8,000.00	CA
105-010A	DISPUTE REVIEW BOARD - THREE MEMBER	15,000.00	CA
201-005A	CLEARING & GRUBBING	2.50	ACRE
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	18.00	EACH
203-005A	REMOVAL OF OBSTRUCTIONS	1.00	LS
203-006A	REMOVAL OF SIGN SINGLE POST	5.00	EACH
203-015A	REMOVAL OF BITUMINOUS SURFACE THICKNESS LESS THAN 6"	3,044.00	SY
203-020A	REMOVAL OF BRIDGE - FULL RIVERTON RD (APPROX 7282 SF)	1.00	EACH
203-075A	REMOVAL OF FENCE	295.00	FT
203-080A	REMOVAL OF GUARDRAIL	1,574.00	FT
203-122A	REMOVAL OF MISCELLANEOUS ITEMS SURFACE-MOUNTED TUBULAR MARKERS	70.00	EACH
205-005A	EXCAVATION	12,314.00	CY
205-040A	GRANULAR BORROW	8,001.00	CY
205-060A	WATER FOR DUST ABATEMENT	1,400.00	MG
205-095A	SOFT SPOT REPAIR	7,500.00	CA
209-005A	SMALL DITCH	53.00	FT
210-005A	STRUCTURE EXCAVATION SCHEDULE NO. 1 SOIL AND GRAVEL	222.00	CY
210-015A	COMPACTING BACKFILL	145.00	CY
212-011A	FIBER WATTLE	1,656.00	FT
212-020A	SILT FENCE	503.00	FT
212-095A	INLET PROTECTION	15.00	EACH
212-115A	EROSION CONTROL MAINTENANCE	110.00	HR
213-010A	TOPSOIL 6"	10,206.00	SY
251-005A	MIGRATORY BIRD TREATY ACT COMPLIANCE	5,000.00	CA
301-010A	GRANULAR SUBBASE	1,800.00	CY
301-010A	GRANULAR SUBBASE	98.00	CY
303-022A	3/4" AGGREGATE TYPE B FOR BASE	2,600.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	100.00	GAL
405-425A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-2	600.00	TON
502-140A	CONCRETE CLASS 40-A SCHEDULE NO. 1	76.30	CY
502-310A	CONCRETE CLASS 40 AF SCHEDULE NO. 2	388.10	CY
502-435A	APPROACH SLAB	346.50	SY
503-010A	METAL REINFORCEMENT SCHEDULE NO. 1	29,146.00	LB
503-015A	METAL REINFORCEMENT SCHEDULE NO. 2	26,074.00	LB
503-020A	EPOXY COATED METAL REINFORCEMENT	37,497.00	LB
504-005A	STEEL BRIDGE RIVERTON RD (APPROX WT 419,625 LBS)	1.00	LS
504-015A	STRUCTURAL STEEL BRIDGE SIGN	181.00	LB
504-040A	COMB PED/BICYCLE & TRAF RAILING	516.90	FT
505-105A	PROVIDE & DRIVE 14" DIA STEEL SHELL PILE	1,090.00	FT
505-155A	PROV&DRIV TEST STEEL SHELL PILE (14")	201.00	FT
505-205A	PROV&INST 14" DIA PILE SHOES OR TIPS	28.00	EACH
505-215A	SPLICE STEEL PILE BEFORE DRIVING	3.00	EACH
505-215B	SPLICE STEEL PILE DURING DRIVING	3.00	EACH
507-005A	ELASTOMERIC BEARINGS PLAIN (0.5" x 10" x 2'-0"	21.00	EA

520-005A	PREDRILLING FOR PILING IN SOIL	641.00	FT
521-005A	DYNAMIC PILE TESTING	3.00	EA
521-010A	CAPWAP ANALYSIS	6.00	EA
566-005A	COMPRESSION EXPANSION JOINT 3"	90.00	FT
576-005A	(GFRP) REINFORCEMENT	480.00	FT
577-005A	PILE SLEEVES 24" DIA	252.00	FT
584-005A	TEMPORARY SHORING TTC WALL NB 1 APPROX SF=1052	1.00	LS
584-005A	TEMPORARY SHORING TTC WALL NB 2 APPROX SF=1040	1.00	LS
584-005A	TEMPORARY SHORING TTC WALL SB 1 APPROX SF=1040	1.00	LS
584-005A	TEMPORARY SHORING TTC WALL SB 2 APPROX SF=987	1.00	LS
586-005A	UTILITY CONDUIT COMPLETE INSTALLATION WITH HANGERS (APPROX 2405')	1.00	LS
605-025A	12" STORM SEWER PIPE	913.00	FT
605-605A	INLET TYPE 1	15.00	EACH
608-025A	12" APRON FOR PIPE	3.00	EACH
610-030A	FENCE TYPE 3 B	225.00	FT
610-035A	FENCE TYPE 4 BRIDGE	154.40	FT
610-035A	FENCE TYPE 4 ROADWAY	1,229.00	FT
610-250A	BRACES	12.00	EACH
612-005A	W-BEAM GUARDRAIL	1,328.00	FT
612-115C	GUARDRAIL TERMINAL, TANGENT	4.00	EACH
612-120A	GUARDRAIL TRANSITION, LOW SPEED	4.00	EACH
612-150A	PRECAST CONCRETE BARRIER	1,040.00	FT
613-035A	CRASH CUSHION, LOW MAINTENANCE	2.00	EACH
614-015A	SIDEWALK	1,042.00	SY
614-025A	CURB RAMP	32.00	SY
615-492A	CURB & GUTTER TYPE 2	1,922.00	FT
616-010A	SIGN TYPE B-1	42.50	SF
616-040J	STEEL SIGN POST TYPE E-1	96.50	FT
616-040K	STEEL SIGN POST TYPE E-2	10.50	FT
617-045A	DELINEATOR TYPE 9	36.00	EACH
621-005A	SEED BED PREPARATION	3.10	ACRE
621-010A	SEEDING	3.10	ACRE
621-035A	FERTILIZING	3.10	ACRE
621-050A	SOIL AMENDMENT	3.10	ACRE
621-060A	MULCH PLUS TACKIFIER	3.10	ACRE
624-005A	LOOSE RIPRAP	20.00	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	2,742.00	SF
626-040A	BARRICADE TYPE 3	10.00	EACH
626-050A	DRUMS	184.00	EACH
626-065A	ARROW BOARD	620.00	HR
626-100B	MISC TEMPORARY TRAF CONT ITEMS	50,000.00	CA
626-105A	TEMPORARY TRAFFIC CONTROL MAINTENANCE	250.00	HR
626-112A	FLOOD LIGHTS	920.00	HR
626-115A	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	50.00	DAY
626-116A	TEMPORARY CONCRETE BARRIER OR APPROVED EQUAL	3,457.00	FT
626-117A	R&R TEMP CONCRETE BARRIER OR APPROVED EQUAL	2,313.00	FT
626-118A	TEMPORARY CRASH CUSHION	8.00	EACH
626-121A	R&R TEMP CRASH CUSHION	3.00	EACH

626-135A	WEIGHTED BASE TUBULAR MARKERS	178.00	EACH
626-140A	SURFACE-MOUNTED TUBULAR MARKERS	70.00	EACH
630-025A	LONG PAV MKG - WATERBORNE	110,492.00	FT
640-010A	RIPRAP/EROSION CONTROL GEOTEXTILE	78.00	SY
650-005A	TIME-LAPSE CAMERA	1.00	EACH
650-010A	TIME-LAPSE CAMERA SERVICE	8.00	MO
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING AS NEEDED FOR 677-005A	10,000.00	CA
675-010A	DIRECTED SURVEYING CREW	10,000.00	CA
675-010A	DIRECTED SURVEYING OFFICE COMPUTATIONS	20,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S501-17A	MSE RETAINING WALL ROADWAY	17,955.00	SF
S501-17A	MSE RETAINING WALL BRIDGE	7,825.00	SF
S501-20A	SP BRIDGE PRECAST COLUMN	3.00	EACH
S501-20B	SP BRIDGE PRECAST PIER CAP	1.00	EACH
S501-20C	SP BRIDGE SCREW ANCHORS (BRIDGE SIGN)	16.00	EACH
S501-20D	SP BRIDGE INSTALL BRIDGE SIGN	2.00	EACH
S501-25A	SP BRIDGE TEMPORARY PROTECTION FOR FUTURE GRADE LOWERING	1.00	LS
S501-30A	SP BRIDGE FENCE DECORATIVE PANELS	510.90	FT
S501-30B	SP BRIDGE PROTECTIVE FENCE FOR COMBINATION RAILING	510.90	FT
S501-40A	SP BRIDGE CONCRETE CLASS 50 AF	68.00	CY
S501-70A	PAINTING CONCRETE (BRIDGE)	7,197.00	SF
S501-70A	PAINTING CONCRETE (ROADWAY)	13,160.00	SF
S900-50B	CONTINGENCY AMOUNT CONTRACTOR DESIGN FOR THE CITY OF BLACKFOOT SEWER MANHOLES	35,000.00	CA
S901-05N	SP JUNCTION BOX	8.00	EACH
S901-06D	SP CONSTRUCTION ENTRANCE/EXIT TEMPORARY CRASH CUSHION	4.00	EACH
S904-05F	SP TRAFFIC CONTROL MANAGER	1.00	LS
S911-05C	SP REMOVAL OF PIPE (8"-24")	242.00	FT
S911-05H	SP LINEAR DELINEATION SYSTEM	1,568.00	FT
S911-05Q	SP 4" HDPE UTILITY CONDUIT (4 EA)	1,289.00	FT
S913-05A	SP STORMWATER BERM	151.00	CY
S913-05F	SP LAVA ROCK (LOAD, HAUL, AND PLACE)	62.70	CY
S913-05F	SP LAVA ROCK (LOAD, HAUL, AND PLACE)(BRIDGE)	5.00	CY
S916-05A	SP TRUCK MOUNTED ATTENUATOR	7.00	DAY
Z629-05A	MOBILIZATION BRIDGE	1.00	LS
Z629-05A	MOBILIZATION ROADWAY	1.00	LS