



Idaho Transportation Department  
 Bid Results  
 for  
 April 2, 2019  
 Final Bid Results April 4, 2019

<b>Project No.</b>	A020(162)		
<b>Location</b>	STC-3738, Strike Dam Road Improvements, Mountain Home Hwy. District		
<b>District No.</b>	LHTAC(3)	<b>County</b>	Elmore
<b>Key No.</b>	20162		
		<b>City</b>	<b>State</b>
		<b>Bid Amount</b>	
<b>Contract Awarded 06/07/2019</b>			
Engineer's Estimate			\$583,421.36
Robison Logging & Excavation	Grand View	ID	Regular \$691,209.76
Knife River Corporation-Mountain West	Boise	ID	Regular 731,227.00
Concrete Placing Company., Inc.	Boise	ID	Regular 1,011,875.75
Sunroc Corporation	Boise	ID	Regular 1,154,570.00
Staker & Parson Companies DBA Idaho Materials Construction	Nampa	ID	Irregular <del>1,558,385.00</del>
			<b><u>Bid Abstract</u></b>

<b>Project No.</b>	A020(109)		
<b>Location</b>	STC-7664, 6 <sup>th</sup> Street Pedestrian Improvements, Moscow		
<b>District No.</b>	LHTAC(2)	<b>County</b>	Latah
<b>Key No.</b>	20109		
		<b>City</b>	<b>State</b>
		<b>Bid Amount</b>	
<b>This project has been rejected and may re-bid at later date</b>			
McCall's Classic Construction	Clarkston	WA`	Regular \$189,080.50
Coyote Pak LLC DBA Coyote Pak Construction	Sandpoint	ID	Irregular <del>248,234.50</del>

<b>Project No.</b>	A012(019)		
<b>Location</b>	Orofino Creek Bridge Road		
<b>District No.</b>	LHTAC(2)	<b>County</b>	Clearwater
<b>Key No.</b>	12019		
<b>Bidder</b>			
<b>City</b>			
<b>State</b>			
<b>Bid Amount</b>			
<b>This project has been cancelled and may re-bid at later date</b>			
Clearwater Construction & Management LLC	Spokane	WA	Irregular \$1,836,922.00

<b>Project No.</b>	A020(752)		
<b>Location</b>	SMA-7072, Int. Washington Street & Caswell Avenue, Twin Falls		
<b>District No.</b>	LHTAC(4)	<b>County</b>	Twin Falls
<b>Key No.</b>	20752		
<b>Bidder</b>			
<b>City</b>			
<b>State</b>			
<b>Bid Amount</b>			
<b>Contract Awarded 06/03/2019</b>			
Engineer's Estimate			\$195,651.00
Electric 1 West Inc. DBA Balanced Rock Electric	Twin Falls	ID	Regular \$258,752.35
Angle & Associates	Pocatello	ID	Regular 277,054.34
			<a href="#"><b>Bid Abstract</b></a>

<b>Project No.</b>	A020(211)		
<b>Location</b>	SMA-7895, Kootenai Cutoff Road Pedestrian Improvements, Ponderay		
<b>District No.</b>	LHTAC(1)	<b>County</b>	Bonner
<b>Key No.</b>	20211		
<b>Bidder</b>		<b>City</b>	<b>State</b>
<b>Contract Awarded 06/07/2019</b>			
Engineer's Estimate			\$115,055.68
Interstate Concrete & Asphalt	Rathdrum	ID	Regular \$154,732.34
Earthwork Northwest	Sandpoint	ID	Irregular <del>163,391.00</del>
Coyote Pak LLC DBA Coyote Pak Construction	Sandpoint	ID	Irregular 214,403.00
TML Construction Inc.	Hayden	ID	Regular 219,307.25
			<a href="#"><u>Bid Abstract</u></a>

<b>Project No.</b>	A013(874)		
<b>Location</b>	STC-5740, W. Riverview Drive, Post Falls Hwy. District		
<b>District No.</b>	LHTAC(1)	<b>County</b>	Kootenai
<b>Key No.</b>	13874		
<b>Bidder</b>		<b>City</b>	<b>State</b>
<b>Contract Awarded 06/18/2019</b>			
Engineer's Estimate			\$682,574.00
Northwest Grading Inc.	Coeur d' Alene	ID	Regular \$531,577.55
T LaRiviere Equipment & Excavation	Athol	ID	Regular 753,528.00
			<a href="#"><u>Bid Abstract</u></a>

<b>Project No.</b>	A019(862)		
<b>Location</b>	US-93, Gibbonsville to Montana Line		
<b>District No.</b>	6	<b>County</b>	Lemhi
<b>Key No.</b>	19862		
	<b>Bidder</b>	<b>City</b>	<b>State</b>
	<b>Contract Awarded 06/13/2019</b>		
	Engineer's Estimate		\$4,500,344.82
	H-K Contractors Inc.	Idaho Falls	Regular \$5,217,769.00
	Depatco Inc.	St. Anthony	Regular 5,723,888.68
			<b><u>Bid Abstract</u></b>

\*\*\*\*\* END \*\*\*\*\*