

Key No. 21983 - N 500 W RECONSTRUCTION
Teton County

Item No	Description	QTY	Unit
107-019A	SURVEY MONUMENT PRESERVATION	10,000.00	CA
201-005A	CLEARING & GRUBBING	9.70	ACRE
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	76.00	EACH
203-006A	REMOVAL OF SIGN	12.00	EACH
203-123A	REMOVAL OF MISCELLANEOUS ITEMS - PIPE	442.00	FT
205-005A	EXCAVATION	7,182.00	CY
205-030A	BORROW	2,714.00	CY
205-060A	WATER FOR DUST ABATEMENT	1,500.00	MG
205-071A	EXCAVATION AND REPAIR OF SOFT SPOTS	1,000.00	CY
209-005A	SMALL DITCH	28.00	FT
212-011A	FIBER WATTLE	8,661.00	FT
212-105A	WATER AND POLLUTION	5,000.00	CA
301-005A	GRANULAR SUBBASE	12,280.00	TON
303-021A	3/4" AGGREGATE TYPE A FOR BASE	28,490.00	TON
308-015A	PULVERIZE EXISTING SURFACE	34,345.00	SY
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	100.00	GAL
405-245A	APPROACH - ASPHALT	22.00	EACH
405-245B	APPROACH - GRAVEL	11.00	EACH
405-425A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-2	7,820.00	TON
602-035A	18" PIPE CULVERT	655.00	FT
602-045A	24" PIPE CULVERT	7.00	FT
602-055A	30" PIPE CULVERT	21.00	FT
602-065A	36" PIPE CULVERT	168.00	FT
602-250A	PIPE ARCH - (20" x 28")	16.00	FT
602-250A	PIPE ARCH - (47"x71")	57.00	FT
608-035A	18" APRON FOR PIPE	14.00	EACH
612-005A	W-BEAM GUARDRAIL	12.50	FT
612-050A	GUARDRAIL TERMINAL	1.00	EACH
612-120B	GUARDRAIL TRANSITION, HIGH SPEED	1.00	EACH
612-150A	CONCRETE BARRIER	187.50	FT
612-155A	CONCRETE TERMINAL TY A	1.00	EACH
616-010A	SIGNS TY B	250.00	SF
616-035A	SIGN BRACKETS & BRACE ANGLES	127.10	LB
616-050A	BRKAWY STL SIGN POST TY E	1,207.20	LB
616-070A	BRKAWY STL SIGN POST INST TY E	28.00	EACH
618-025A	STREET MONUMENT	8.00	EACH
621-005A	SEED BED PREPARATION	1.82	ACRE
621-010A	SEEDING - ROADSIDE	1.80	ACRE
621-010B	SEEDING - WETLAND	0.02	ACRE
624-005A	LOOSE RIPRAP	62.00	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	1,211.00	SF
626-050A	DRUMS	40.00	EACH
626-100A	MISC TEMPORARY TRAF CONT ITEMS	5,000.00	CA
626-105A	TRAF CNTL MAINTENANCE	140.00	HR
626-120A	FLAGGER CONTROL	1,800.00	HR

626-125A	PILOT CAR	700.00	HR
626-135A	WEIGHTED BASE TUBULAR MARKERS	210.00	EACH
630-025A	LONG PAV MKG - WATERBORNE	112,120.00	FT
634-005A	MAILBOX - TYPE A	7.00	EACH
634-005B	MAILBOX - TYPE B	3.00	EACH
640-010A	RIPRAP/EROSION CONT GEOTEXTILE	565.00	SY
640-015A	SUBGRADE SEPARATION GEOTEXTILE	3,000.00	SY
654-025A	COMPOST	3.64	ACRE
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	10,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S501-15A	RETAINING WALL	1,250.00	SF
S900-50A	CONTINGENCY AMOUNT - MISCELLANEOUS WORK	5,000.00	CA
S901-05A	SP - MAILBOX CLUSTER (16 MAILBOXES, 2 PARCE L LOCKERS)	1.00	EACH
Z629-05A	MOBILIZATION	1.00	LS