

Key No. 23345 - I-84, HEYBURN IC  
Minidoka County

Item No	Description	QTY	Unit
104-005A	PARTNERING	30,000.00	CA
105-010A	DISPUTE REVIEW BOARD - THREE MEMBER	110,000.00	CA
107-019A	SURVEY MONUMENT PRESERVATION	10,000.00	CA
201-005A	CLEARING & GRUBBING	40.51	ACRE
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	11.00	EACH
203-002A	REMOVAL OF OBSTRUCTIONS (CRASH CUSHION)	4.00	EACH
203-003A	REMOVAL OF OBSTRUCTIONS (PIPE)	1,588.00	FT
203-006A	REMOVAL OF SIGN	87.00	EACH
203-007A	REMOVAL OF SIGN (OVERHEAD)	6.00	EACH
203-015A	REMOVAL OF BITUMINOUS SURFACE	132,213.00	SY
203-020A	REMOVAL OF BRIDGE - FULL (MULTSPAN, WB)	1.00	EACH
203-020B	REMOVAL OF BRIDGE - FULL (MULTISPAN, EB)	1.00	EACH
203-065A	REMOVAL OF CURB	220.00	FT
203-075A	REMOVAL OF FENCE	17,975.00	FT
203-080A	REMOVAL OF GUARDRAIL	3,213.00	FT
203-080B	REMOVAL OF BARRIER	1,509.00	FT
203-090A	REMOVAL OF INLET	2.00	EACH
203-122A	REMOVAL OF MISCELLANEOUS ITEMS (LUMINAIRE)	28.00	EACH
203-130A	REMOVAL OF PAVEMENT MARKINGS	31,064.00	FT
203-130B	REMOVAL OF PAVEMENT MARKINGS	159.00	SF
204-006A	OBLITERATION OF OLD ROAD	1.00	LS
205-005A	EXCAVATION	134,235.00	CY
205-030A	BORROW	261,003.00	CY
205-040A	GRANULAR BORROW	58,974.00	CY
205-060A	WATER FOR DUST ABATEMENT	3,000.00	MG
205-071A	EXCAVATION AND REPAIR OF SOFT SPOTS	1,000.00	CY
209-005A	SMALL DITCH	965.00	FT
210-005A	STRUCTURE EXCAVATION SCHEDULE NO. 1	2,337.00	CY
210-015A	COMPACTING BACKFILL	1,324.00	CY
212-011A	FIBER WATTLE	36,260.00	FT
212-060A	STABILIZED CONSTRUCTION ENTRANCE	6.00	EACH
212-095A	INLET PROTECTION (INSERT)	1.00	EACH
212-095B	INLET PROTECTION	6.00	EACH
212-105A	WATER AND POLLUTION	50,000.00	CA
251-005A	MIGRATORY BIRD TREATY ACT COMPLIANCE	20,000.00	CA
301-005A	GRANULAR SUBBASE	124,580.00	TON
301-010A	GRANULAR SUBBASE	1,498.00	CY
303-021A	3/4" AGGREGATE TYPE A FOR BASE	53,740.00	TON
303-022A	3/4" AGGREGATE TYPE B FOR BASE	48,899.00	TON
304-010A	RECONDITIONING	77.00	STA
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	23,500.00	GAL
403-300A	CHIP SEAL COAT WARRANTY	145,077.00	SY
405-240A	MISCELLANEOUS PAVEMENT	154.00	SY
405-245A	APPROACH (COMMERCIAL)	1.00	EACH
405-455A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-5 (NMAS 1/2", PG 76-	35,507.00	TON

	28)		
405-455B	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-5 (NMA5 1/2", PG 64-28)	24,753.00	TON
405-455C	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-5 (T)	16,234.00	TON
431-005A	COLD MILLING	7,851.00	SY
502-065A	CONCRETE CLASS 40 AF	249.10	CY
502-140A	CONCRETE CLASS 40-A SCHEDULE NO. 1	3,233.80	CY
502-310A	CONCRETE CLASS 40 AF SCHEDULE NO. 2	2,507.00	CY
502-430A	CONCRETE PARAPET (42" SINGLE SLOPE)	2,868.20	FT
502-435A	APPROACH SLAB	857.10	SY
503-010A	METAL REINFORCEMENT SCHEDULE NO. 1	716,222.00	LB
503-015A	METAL REINFORCEMENT SCHEDULE NO. 2	224,587.00	LB
503-020A	EPOXY COATED METAL REINFORCEMENT	423,923.00	LB
504-005A	STEEL BRIDGE (APPROX. WEIGHT 2606308 LBS)	1.00	LS
504-005B	STEEL BRIDGE (APPROX. WEIGHT 1864810 LBS)	1.00	LS
504-005C	STEEL BRIDGE (APPROX. WEIGHT 181729 LBS)	1.00	LS
505-110A	PROVIDE & DRIVE 16" DIA STEEL SHELL PILE	12,525.00	FT
505-115A	PROVIDE & DRIVE 18" DIA STEEL SHELL PILE	18,774.00	FT
505-160A	PROV&DRIV TEST STEEL SHELL PILE (16")	641.00	FT
505-165A	PROV&DRIV TEST STEEL SHELL PILE (18")	574.00	FT
505-215A	SPLICE STEEL PILE BEFORE DRIVING	434.00	EACH
505-215B	SPLICE STEEL PILE DURING DRIVING	476.00	EACH
507-005A	ELASTOMERIC BEARINGS PLAIN (SIZE 1/2"X8"X14")	10.00	EA
507-010A	ELASTOMERIC BEARINGS LAMINATED (26" DIA)	24.00	EA
507-010B	ELASTOMERIC BEARINGS LAMINATED (SIZE 1 1/2"X12"X18")	5.00	EA
507-015A	PTFE BEARINGS	24.00	EA
511-005A	CONCRETE WATERPROOF SYSTEM (TYPE C)	280.00	SY
521-005A	DYNAMIC PILE TESTING	13.00	EA
521-010A	CAPWAP ANALYSIS	26.00	EA
551-005A	PREPARED & PLACED PPC OVERLAY	9,693.40	SY
551-010A	FURNISHED PPC OVERLAY MATERIAL	235.70	CY
566-010A	COMPRESSION EXPANSION JOINT (PER PLAN)	95.30	FT
567-005A	STRIP SEAL EXPANSION JOINT	187.80	FT
574-005A	ANTI-GRAFFITI COATING	43,180.00	SF
575-005A	TEXTURED CONCRETE SURFACE	787.00	SY
576-005A	(GFRP) REINFORCEMENT	430.00	FT
577-005A	PILE SLEEVES (24")	2,324.00	FT
584-005A	TEMPORARY SHORING	1.00	LS
584-005B	TEMPORARY SHORING (ROADWAY)	1.00	LS
586-005A	UTILITY CONDUIT	1.00	LS
602-035A	18" PIPE CULVERT	60.00	FT
602-045A	24" PIPE CULVERT	945.00	FT
605-035A	18" STORM SEWER PIPE	124.00	FT
605-045A	24" STORM SEWER PIPE	671.00	FT
605-616A	INLET TYPE 3A	1.00	EACH
605-630A	INLET TYPE 8	7.00	EACH
608-035A	18" APRON FOR PIPE	2.00	EACH
608-045A	24" APRON FOR PIPE	12.00	EACH
608-210A	METAL SAFETY APRON (CROSS DRAINAGE) 24"	2.00	EACH

610-030A	FENCE TY 3 B	14,897.00	FT
610-035A	FENCE TY 4 (42" ON COPING)	1,905.00	FT
610-035A	FENCE TY 4 (8' W/ BARBARM)	1,690.00	FT
610-035B	FENCE TY 4 B (8' TALL)	40.00	FT
610-200A	GATE TY 3	4.00	EACH
610-250A	BRACES	76.00	EACH
611-001A	CATTLE GUARD	2.00	EACH
612-005A	W-BEAM GUARDRAIL	7,876.00	FT
612-050A	GUARDRAIL TERMINAL	10.00	EACH
612-110A	GUARDRAIL ANCHOR	10.00	EACH
612-120A	GUARDRAIL TRANSITION, LOW SPEED	4.00	EACH
612-120B	GUARDRAIL TRANSITION, HIGH SPEED	12.00	EACH
612-150A	CONCRETE BARRIER	1,876.00	FT
612-155A	CONCRETE TERMINAL TY A	2.00	EACH
613-025A	CRASH CUSHION, SACRIFICIAL-METAL (BULLNOSE)	2.00	EACH
613-035A	CRASH CUSHION, LOW MAINTENANCE	1.00	EACH
615-256A	CURB TYPE 1	1,239.00	FT
615-260A	CURB TYPE 5	51.00	FT
616-010A	SIGNS TY B	918.00	SF
616-015A	SIGNS TY C	3,946.00	SF
616-031A	OVERHEAD CANTILEVER SIGN STRUCTURE SPAN 34 FT	1.00	EACH
616-031B	OVERHEAD CANTILEVER SIGN STRUCTURE SPAN 28 FT	2.00	EACH
616-031C	OVERHEAD CANTILEVER SIGN STRUCTURE SPAN 52 FT	2.00	EACH
616-035A	SIGN BRACKETS & BRACE ANGLES	2,448.00	LB
616-040A	BRKAWY STL SIGN POST TY A	10,288.00	LB
616-045A	BRKAWY STL SIGN POST TY B	1,691.00	LB
616-050A	BRKAWY STL SIGN POST TY E	89.00	LB
616-055A	BRKAWY WOOD SIGN POST TY D	3.95	MFBM
616-060A	BRKAWY STL SIGN POST INST TY A	32.00	EACH
616-065A	BRKAWY STL SIGN POST INST TY B	14.00	EACH
616-070A	BRKAWY STL SIGN POST INST TY E	3.00	EACH
616-080A	REINSTALL SIGNS	25.00	EACH
617-005A	DELINEATOR TY 1	195.00	EACH
617-010A	DELINEATOR TY 2	32.00	EACH
617-020A	DELINEATOR TY 4	2.00	EACH
617-045A	DELINEATOR TY 9	75.00	EACH
617-050A	MILEPOST TY 1	2.00	EACH
619-010A	ILLUMINATION TY 2	1.00	LS
621-005A	SEED BED PREPARATION	44.40	ACRE
621-010A	SEEDING (PERMANENT)	44.40	ACRE
621-010B	SEEDING (TEMPORARY)	36.62	ACRE
624-005A	LOOSE RIPRAP D50 = 6"	90.00	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	2,733.00	SF
626-040A	BARRICADE TY 3	8.00	EACH
626-050A	DRUMS	756.00	EACH
626-076A	ARROW BOARD TY C	2,650.00	HR
626-093A	TEMP PAV MARKING - WATERBORNE	227,856.00	FT
626-105A	TRAF CNTL MAINTENANCE	9,000.00	HR
626-112B	FLOOD LIGHTS	66.00	DAY

626-115B	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	6,300.00	DAY
626-116A	TEMP CONCRETE BARRIER	34,701.00	FT
626-117A	R&R TEMP CONCRETE BARRIER	52,054.00	FT
626-118A	TEMP CRASH CUSHION	19.00	EACH
626-119A	TRUCK ATTENUATOR	2.00	EACH
626-120A	FLAGGER CONTROL	48.00	HR
626-121A	R&R TEMP CRASH CUSHION	41.00	EACH
626-130B	TEMPORARY TRAFFIC CONTROL SIGNAL	60.00	DAY
626-140A	SURFACE-MOUNTED TUBULAR MARKERS	20.00	EACH
630-010A	T,W,S,A PAVEMENT MARKINGS - PREF THERMO	1,316.00	SF
630-025A	LONG PAV MKG - WATERBORNE	191,353.00	FT
631-010A	RUMBLE STRIPS	4.20	MILE
640-010A	RIPRAP/EROSION CONT GEOTEXTILE	272.20	SY
640-015A	SUBGRADE SEPARATION GEOTEXTILE	202,800.60	SY
645-015A	C4 SP3 & SP5 FIELD LAB	1.00	LS
650-005A	TIME-LAPSE CAMERA	2.00	EACH
650-010A	TIME-LAPSE CAMERA SERVICE	68.00	MO
654-025A	COMPOST (UNGULATE MANURE)	118.96	ACRE
656-005A	TRAF SIGNAL INSTALLATION	1.00	LS
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	20,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S501-17A	MSE RETAINING WALL	31,131.00	SF
S501-20A	SP BRIDGE DRILLED SHAFT FOUNDATION FOR OVERHEAD SI GN STRUCTURE	5.00	EACH
S501-25A	SP BRIDGE SETTLEMENT MONITORING	1.00	LS
S501-25B	SP BRIDGE SETTLEMENT MONITORING (WB)	1.00	LS
S501-30A	SP BRIDGE EXPANSION JOINT, MODULAR	189.00	FT
S501-30B	SP BRIDGE PROTECTIVE FENCE FOR CONCRETE PARAPET	2,478.60	FT
S501-40A	SP BRIDGE CELLULAR CONCRETE	4,331.00	CY
S900-50A	CONTINGENCY AMOUNT DRILLED SHAFT - REMOVAL OF OBSTRUCTIONS	10,000.00	CA
S901-05A	SP FIBER OPTIC SPLICE VAULT	1.00	EACH
S901-05B	SP FIELD OFFICE	1.00	EACH
S904-05A	SP RWIS AND WEATHER SENSOR SYSTEM	1.00	LS
S911-05A	SP 36" CURED-IN-PLACE PIPE	453.00	FT
S912-05A	SP ISLAND CONCRETE	1,231.60	SY
S913-05A	SP ABANDON CULVERT	9.70	CY
Z629-05A	MOBILIZATION	1.00	LS